




THE ATLAS FORWARD SILICON TRACKER

- Overview of the ATLAS SCT
- Module design
- Module production
- Engineering and services
- Macro-assembly and testing
- Summary



Neil Jackson
University of Liverpool




Overview of the SCT


- The SCT forms part of the ATLAS Inner Detector.
- It is constructed using 4088 silicon micro-strip modules arranged as 4 barrels in the central region and 2 x 9 annular wheels in the forward region


The Inner Detector is in a solenoidal 2T field

SCT



Inner Detector (ID)








- The modules are arranged to provide 4 space points per track
 $-2.5 < \eta < 2.5$
- Each module measures two coordinates
 - Detector pitch is $80 \mu\text{m}$ and $\pm 20 \text{ mrad}$ stereo



Inner Detector (ID)

Momentum resolution

$B = 2 \text{ T}$




t tbar Higgs event



Sensors


p in n sensors were procured from Hamamatsu and CIS



Detectors are of excellent quality from Hamamatsu



Pre-Irradiation:

- ◆ All quantities within specification
- ◆ Very low leakage currents
- ◆ >99.9% good readout strips



Post-Irradiation:

- ◆ Within specification for operation at ~400V bias after 10 years of LHC



Charge collection vs bias voltage



Noise vs bias

Typical results from the Hamamatsu detectors

Radiation exposure is $3 \times 10^{14} \text{ p cm}^{-2}$ at 24 GeV/c (10 yrs LHC)



- Modules consist of 4 (2) detectors mounted on a baseboard (barrel) or spine (forward) consisting of Thermal Pyrolytic Graphite + AlN
 - Ensures good thermal performance
- The kapton hybrids are mounted on carbon-carbon substrates
- Modules have 1526 binary readout channels per module
- Spatial resolutions $\sigma_{r\phi} = 16 \mu\text{m}$, $\sigma_R = 580\mu\text{m}$



Forward Module

SiLC Meeting 13 June 2006





Module types






THERMAL MANAGEMENT



- The design aims to isolate the heat from the hybrid from the silicon
- The carbon-carbon cooling block includes a thermal split





Support structures

- All support structures, cylinders and discs, are produced using a sandwich material constructed with carbon fibre skins and a Korex core in industry
- Cu/Ni cooling pipes, precision mounts for modules, power tapes, opto-fibre harnesses + DCS and alignment components are added






MODULE PRODUCTION

- Production of the modules occurs at several sites worldwide
 - 1976 forward modules + spares were constructed in Australia, Germany, Netherlands, Spain, Switzerland and the UK
- Modules must satisfy many criteria and tolerances – e.g.
 - A range of mechanical tolerances, some $< 5 \mu\text{m}$
 - Module leakage current $< 80 \mu\text{A}$ at 350V
 - Noise per channel $< 1500 \text{ ENC}$
 - Average noise occupancy at 1 fC threshold $< 5 \times 10^{-4}$
 - $< 1\%$ bad channels




FORWARD SCT ORGANISATION






A forward module assembly station



Vertical scale is deviation from nominal in units of tolerance.
Horizontal scale is module number.






Bonding and testing




Module bonding



Module in testing



Module metrology







Figure 4: Curves of occupancy versus threshold superimposed for every readout channel of the first readout side of an ABCDST-A module. Every fourth channel (32 in total) of each ASIC appears in each of the boxes.

ATLAS SCT Noise Occupancy - log scale - Fri Apr 20 17:44:09 2001 - RAL R12

Page 1 Run 202 Scan 1 Module 0 (20220170100018)

Mean Noise Occupancy, all channels



Threshold Scans


Noise Occupancy



FORWARD MODULE YIELDS

- Production allowed for a 20% loss in construction and macro assembly
 - **2368 modules were constructed with a yield of 93%**
- ‘Good’ modules satisfied all specifications -> yield 86.3%
- ~50% of the ‘failures’ were just outside over tight metrology specifications
 - A ‘Pass’ category was defined with some parameters limits increased by 50%

Category	Inner	Middle(S+L)	Outer
Good	394	665	984
Pass	39	58	56
Hold/Rework	46	48	23
Fail	16	5	34
Good+Pass (G+P)	433	723	1040
G+P Required to equip End-Caps	400	640	936





Lessons learned



- The progression from prototyping components to full production can introduce some problems and cause delays
 - e.g. Forward hybrid de-lamination problem
- Do not underestimate the time required to optimise techniques and commission equipment
 - e.g. Module assembly techniques
- Take care in defining specifications
 - Achieving the same quality in multiple sites is not straight forward
- Expect unexpected production problems and allow for the time required to solve them
 - Start with a proper contingency to allow for unexpected problems
 - Rigorous prototyping and QA will minimise unexpected problems



Engineering assembly and services


Preparation of discs

- Mounting pads and closeouts are glued onto the disc
- The pads are machined plane
- Patch panels and grounding foils are added
- Services are added
 - Low mass tapes
 - C-C mounting blocks soldered onto Cu/Ni pipes are mounted with high precision
 - Optical fibre harnesses, alignment components and DCS






Metrology results for mounting pin positions for disc 9C



The measurements are repeatable (to $\pm 5 \mu\text{m}$) after thermal cycling



The disc is within specifications



Lessons learned

- Developing new solutions is time consuming
 - e.g. bending and soldering Cu/Ni pipes and developing C-C cooling blocks
- Take care with design of kapton components
 - Design of tracks, attachment of connectors and stiffening where required
- The end-cap support cylinders when delivered were not up to specification and needed modifications involving delays



Macro-assembly



General infrastructure

- The macro-assembly is performed in clean conditions (typically class 10000)
- An evaporative cooling plant based on C_3F_8 is required to cool large numbers of modules
- Special tooling is required to mount modules
 - A manual mounting jig for the end-cap
- Special tooling is required to mount discs into the support
- Testing must be done at $-7C$
 - Requires final power supplies, DCS and DAQ



Mounting modules onto discs

- The disc is mounted in a rotating vertical frame
- Thermal grease is applied to the cooling blocks
- The module is extracted from its frame
- The frame is removed and the module is lined up with the mounting blocks
 - Using the x/y/ θ stages monitored with cameras
- The module is positioned and attached





- Lower modules are added first and then tested electronically and thermally at -7°C . Upper modules next.





Electronic and thermal tests of discs at operating temperature (C_3F_8 coolant at $-25C$)

A disc under test in the environmental chamber



A completed end-cap SCT disk

Close up view




Thermal tests




Mounting discs into the support cylinder

- The disc is extracted from the test frame frame and attached to the tooling to insert it into the cylinder
- After insertion the services are added to the end-cap which is then moved to the cold room for testing.
- The cooling pipes, fibres, low mass tapes and DCS are connected and the disc is readout at -7C .




Endcap C entering
environmental chamber



Endcap C after the insertion of the
last disc



Tests were performed on each disc separately
and on quadrants of discs 7,8 and 9 simultaneously



**Average Input Noise (ENC)
at ~0C:**

- **Outers: 1576**
- **Middles: 1529**
- **Inners: 1070**
- **Short Middles: 907**


Noise measurements from the 9 discs

A total of 99.73% channels are fully functional




Endcap C arrives at CERN

Unloading



Endcap C
in SR1

Transfer
to SR1



Inside
view



Current Status



- Acceptance tests are completed
- Mechanical work is underway
 - Mounted on cantilever stand
 - Support wings and thermal enclosures are being added
- Insertion into TRT in September
- Installation in ATLAS in November



SUMMARY

- ATLAS SCT Endcap C has been completed and shipped to CERN
 - Module production was completed on time with a successful yield
 - Acceptance testing in Liverpool and at CERN was completed
 - The completion of the mechanical structure, installation inside the TRT and joint testing will precede installation in ATLAS
- Several problems have been solved on route
 - No show stoppers
 - But usually caused delays and resource implications
- The schedule for completion remains tight but the collaboration is now looking forward to the first physics